



Section 2

EROSION PREVENTION AND SEDIMENT CONTROL PLAN

2.1 Requirements

Glasgow, KY will require an Erosion Prevention and Sediment Control (EPSC) Plan for most types of development construction. When preparing the EPSC Plan, the design engineer and/or developer should determine the best practices to protect active construction sites by selecting source control and sediment containment practices. In doing so, most erosion problems can be avoided and sediment containment issues can be addressed prior to construction disturbances.

Site characteristics such as soil types, topography, slopes, and geography, and construction methods should be thoroughly reviewed when selecting BMPs to implement throughout the life of the project. The design team should be mindful of how the site is changing throughout the project so that BMPs can be repaired, modified or replaced with a more suitable practice.

For more information regarding the required elements of an EPSC Plan, refer to **Appendix B – EPSC Plans**.